KADUR DIVISION.

Dated 31st May 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 1st July 1912, for restoring the Kuruvangi Nettikere, Registered No. 626 of Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st May 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Kuruvangi Nettikere, Registered No. 626 of Chikmagalur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Royalty to be paid to Government will have to be borne by the contractor.

Abstract estimate for restoring the Kuruvangi Nettikere, Registered No. 626 of Chikmagalur Taluk, Kadur District.

	Items of work	*Per*	*Quantity*
	Bund to be raised to R. L. 55·00 with side slopes 2 : 1.		
1.	Earthwork to bund including watering, tamping, etc., complete	C. yd.	5,766
2.	New stone work	,,	1,676
3.	Gravel backing to revetment including lead ...	,,	438
4.	Turfing	S. yd.	7,613
5.	Removing and refixing the existing grade stone including painting, etc., complete	Each	20
6.	Do index stone	,,	20
7.	Providing new B. M. stone	,,	2
8.	Do Registered No. stone	,,	1
9.	Do slate stone	,,	1
10.	Do gauge stone	,,	1
11.	Jungle cleaning	Lump sum	Rs.
	Examining the leaks in the right sluice and repairs to it ...	,,	
	Extending the left waste-weir from 20′ to 50′ ...	,,	
1.	Earthwork chargeable to bund (cutting high ground excavating foundation for body wall, etc.) ...	,,	
2.	Dismantling the existing return	,,	
3.	Burnt brick in surki	C. ft.	649
4.	Plastering with surki	Sq.	5·90
5.	Burnt stone slabs	S. ft.	121
6.	Refixing the available coping slab	S. ft.	22
7.	Joints to coping slab	Lump sum	Rs.
8.	Rough stone work, new	C. yd.	58
9.	Old stone work	C. yd.	15
10.	Raising and repairing the existing left return of the right waste-weir	Lump sum	Rs.

R. S. NAVARATNA,
Executive Engineer.